

Fred Marzec & Associates, Inc.
Architects and Planners
99 Colonel Brown Road
Norwich, Ct. 06351
Tel: 860-376-2999
Email: fred@fredmarzec.com

ADDENDUM #2
Conversion of Griswold Senior Center to
Griswold Alternative Ed.
22 Soule Street
Town of Griswold, CT. 06351
Dated April 26, 2023

The following changes to the documents specified above shall become a part of those documents as though bound therein. Acknowledge the receipt of the Addendum in the spaces so provided on the 'Form of Proposal'. Failure to properly acknowledge the receipt of this addendum may subject the bidder to disqualification.

Drawings & Specifications:

Item #1: List of questions by Sarazin Construction, indicated as RFI# 4

1. Will the RFI deadline extend with the bid extension? Refer to Addendum #1.
2. Please clarify what type of daylight-responsive controls shall be installed? Daylight harvesting sensor specification shall be coordinated with the lighting control representative. Sensor shall be compatible with the lighting controls shown in the space.
3. Is there enough room in the existing electrical panels for new circuits to be installed? There should be adequate space within the existing panels for the new circuits shown. Circuits made available during the demolition process shall be used for new circuiting.
4. On drawing E-2, are the new outlets being fed from panel EP-1 or a different panel? Please advise. Per note #7, circuits indicated on this plan are to be fed from panel "EP1" unless otherwise noted. If additional circuits are required, provide circuits from other local area panel(s).
5. Several questions regarding the E-4 electrical drawing:
 - Is there more fire alarm demolition than is depicted on the drawings? Per note #7 on sheet ED-1, existing fire alarm devices shall be removed in their entirety.
 - Are all the FA devices and equipment new or are they existing? New.
 - Are all the added Fire Alarm, exits signs, and emergency lights new? If they are new, are we to pick up nearest circuit for the lighting? Yes, they are new. Emergency lighting shall be circuited ahead of lighting controls.
6. FRP is shown on the Room Finish Schedule on drawing A-4 to be installed in Room F105, New Classroom #1. The extent of the FRP is not shown on the elevations for this room, nor for any other room, and there are no specifications for FRP. Please clarify. There is 'No FRP' (fiber glass reinforced panels) wall panels at Room F105 or in the Project.